

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20629-00-02
Spot: SWNESE Sec/Twnshp/Rge: 32-33S-17W
1629 feet from S Section Line, 979 feet from E Section Line
Lease Name: BRYANT Well #: 1
County: COMANCHE Total Vertical Depth: 5800 feet

Operator License No.: 33699
Op Name: T-N-T ENGINEERING, INC.
Address: 9250 E COSTILLA AVE #510
GREENWOOD VLG, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3300		WITH 2 SX CMT
CIBP		5599		
SURF	8.625	436		WITH 475 SX CMT
PROD	5.5	5799	2200	WITH 325 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/13/2011 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: RICK POPP Company: T-N-T ENGINEERING Phone: (620) 786-5514

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/13/2011 10:55 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 3300' WITH 2 SX CMT. 1ST PLUG AT 870' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 460' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5630	5632		SIMPSON
5608	5612		SIMPSON
5584	5593		SIMPSON
5011	5026		MISSISSIPPI
5006	5008		MISSISSIPPI
4999	5002		MISSISSIPPI
4888	4892		PAWNHEE
4519	4522		IOLA
3374	3382		STOTLER
3358	3362		STOTLER

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 01

RECEIVED
JAN 21 2011
KCC DODGE CITY

Signed Eric MacLaren
RECEIVED (TECHNICIAN)
JAN 27 2011
KCC WICHITA

Form CP-2/3