

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-05468-00-01  
Spot: SWSWSW Sec/Twnshp/Rge: 9-15S-13W  
328 feet from S Section Line, 4985 feet from E Section Line  
Lease Name: ROESNER Well #: 12  
County: RUSSELL Total Vertical Depth: 3200 feet

Operator License No.: 33699  
Op Name: T-N-T ENGINEERING, INC.  
Address: 9250 E COSTILLA AVE #510  
GREENWOOD VLG, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3015		
SURF	8.625	598	0	400 SX
PROD	4.5	3199	0	300 SX

Well Type: EOR UIC Docket No: E07604.6 Date/Time to Plug: 12/06/2010 8:30 AM  
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.  
Proposal Rcvd. from: RICK POPP Company: T-N-T ENGINEERING, INC. Phone: (620) 766-5514

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 500# hulls - 5 sxs gel.  
Perf: 1500' - 830' - 590' - 200'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/06/2010 2:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2900' - pumped 5 sxs gel - followed with 50 sxs cement with 100# hulls.  
Pulled tubing to 1472' - pumped 70 sxs cement with 150# hulls.  
Pulled tubing to 600' - pumped 45 sxs cement - circulated out the backside - closed backside valve - pumped 65 sxs cement - circulated out the Braden head.  
POOH. Topped off casing with 5 sxs cement.  
12/07/2010 - checked on fill-up at 160' down. Topped off with 15 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3056	3153		

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #5110.

Plugged through: TBG

RECEIVED

DEC 21 2010

KCC WICHITA

District: 04

Signed Ray Dinkel

(TECHNICIAN)

CM