

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-22944-00-00  
Spot: NENESWSW Sec/Twnshp/Rge: 9-15S-13W  
1257 feet from S Section Line, 4040 feet from E Section Line  
Lease Name: ROESNER Well #: 17  
County: RUSSELL Total Vertical Depth: 3409 feet

Operator License No.: 33699  
Op Name: T-N-T ENGINEERING, INC.  
Address: 9250 E COSTILLA AVE #510  
GREENWOOD VLG, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	566	0	375 SX
PROD	5.5	3431	0	200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/07/2010 10:00 AM  
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.  
Proposal Rcvd. from: RICK POPP Company: T-N-T ENGINEERING, INC. Phone: (620) 786-5514

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 10 sxs gel.  
Perf: 1500' - 850' - 520'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/07/2010 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3348' - pumped 10 sxs gel - followed with 75 sxs cement with 100# hulls.  
Pulled tubing to 1550' - pumped 100 sxs cement with 100# hulls.  
Pulled tubing to 550' - pumped 55 sxs cement - circulated out backside - closed valve on backside - pumped 85 sxs cement - circulated out Braden head.

Perfs:

Top	Bot	Thru	Comments
3068	3080		

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #5111.

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

RECEIVED  
DEC 21 2010  
KCC WICHITA

Form CP-2/3

DEC 16 2010