

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23679-00-00  
Spot: SWSNWNW Sec/Twnshp/Rge: 1-11S-14W  
1199 feet from N Section Line, 779 feet from W Section Line  
Lease Name: CEDERBERG 'A' Well #: 1-1  
County: RUSSELL Total Vertical Depth: 3367 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	254		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/18/2010 2:00 PM  
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC  
Proposal Rcvd. from: BRAD Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE WitnessType: NONE  
Date/Time Plugging Completed: 12/18/2010 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

1st. Plug at 920' w/25 sxs.  
2nd. Plug at 510' w/100 sxs.  
3rd. Plug at 310' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

RECEIVED  
DEC 27 2010  
KCC WICHITA

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM