

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-049-22425-00-00

Spot: SWSWSE

Sec/Twnshp/Rge: 1-31S-8E

378 feet from S Section Line, 2291 feet from E Section Line

Lease Name: KELLEY

Well #: 1-A

County: ELK

Total Vertical Depth: 1771 feet

Operator License No.: 3591

Op Name: TRIBOULET, ED DBA C & E OIL CO.

Address: RR1 BOX 1B2
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	52		60 SX CMT

T1	2.375	1675		
----	-------	------	--	--

PROD	4.5	1764		244 SX CMT
------	-----	------	--	------------

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/09/2010 8:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from:

Company:

Phone:

Proposed
Plugging
Method:

Clean hole, 50' plug at TD, 50 plug at 900' and 550' to surface.

Plugging Proposal Received By: DUANE SIMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed 06/09/2010 12:00 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1700' gelled hole and spotted 10 sack plug. Pulled 1" up to 900' and spotted another 10 sack plug. Pulled 1" up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 80 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1650	1664		

RECEIVED

NOV 30 2010 DAS


KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

RECEIVED

DEC 17 2010 Form CP-2/3

KCC WICHITA