

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-22160-00-00  
Spot: NESESW Sec/Twnshp/Rge: 20-30S-8W  
990 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: CARRICK Well #: 1  
County: KINGMAN Total Vertical Depth: 4494 feet

Operator License No.: 31191  
Op Name: R & B OIL & GAS, INC.  
Address: 912 N LOGAN PO BOX 195  
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	270		195 SX
T1	2.875	4230		
PROD	5.5	4494	3320	165 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/21/2010 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK THE PERFS 50' ABOVE AND CAP WITH 5 SKS OF CMT. RECOVER CASIG. 35 SKS AT 1350', 35 SKS 850', CIRC CMT FROM 320'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/21/2010 11:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4230' AND CAPPED WITH 5 SKS OF CMT. THE CASIG WAS RECOVERED FROM 3320', AND PULLED TO 1350', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 850', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 320', WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4290	4320	CSG	

Remarks: QUALITY WELL SERVICE COMMON CMT

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
AUG 02 2010

KCC WICHITA