

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23488-00-00
Spot: NW Sec/Twnshp/Rge: 13-32S-11W
1320 feet from N Section Line, 1320 feet from W Section Line
Lease Name: HRENCHER Well #: B1
County: BARBER Total Vertical Depth: 3807 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 912 N LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	254		WITH 175 SX CMT
PROD	4.5	3786	2470	WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/02/2010 8:45 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 3560' & 4 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/02/2010 9:50 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 3560' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT WITH 3% CC & 100# HULLS. 2ND PLUG AT 280' WITH 50 SX CMT WITH 3% CC & 100# HULLS. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3616	3626		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED

AUG - 6 2010

KCC DODGE CITY

RECEIVED

AUG 12 2010

KCC WICHITA

Form CP 2/3