

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-20840-00-02  
Spot: NESE Sec/Twnshp/Rge: 11-32S-10W  
1980 feet from S Section Line, 660 feet from E Section Line  
Lease Name: SCHREINER "C" Well #: 1 "OWWO"  
County: BARBER Total Vertical Depth: 4597 feet

Operator License No.: 31191  
Op Name: R & B OIL & GAS, INC.  
Address: 912 N LOGAN PO BOX 195  
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	244		WITH 250 SX CMT
PROD	5.5	4597	3275	WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/28/2010 12:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 4380' & 5 SX CMT. PLUG AT 600' WITH 10S X GEL & 50 SX CMT. PLUG AT 270' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/28/2010 1:20 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 4380' & PUT 5 SX CMT ON TOP OF SAND BRIDGE. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT W/3% CC & 100# HULLS. 2ND PLUG AT 270' WITH 50 SX CMT WITH 3% CC & 100# HULLS. 3RD PLUG AT 40' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4430	4450		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED

AUG -6 2010

KCC DODGE CITY

RECEIVED

AUG 12 2010

KCC WICHITA

Form 02-23