

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-21789-00-00  
Spot: NESENE Sec/Twnshp/Rge: 31-32S-10W  
1650 feet from N Section Line, 330 feet from E Section Line  
Lease Name: VICKERY A Well #: 2  
County: BARBER Total Vertical Depth: 4830 feet

Operator License No.: 31191  
Op Name: R & B OIL & GAS, INC.  
Address: 912 N LOGAN PO BOX 195  
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	265		WITH 175 SX CMT
PROD	4.5	4823	3350	WITH 165 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/30/2010 8:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/30/2010 9:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED DOWN 4 1/2" CASING WITH 200# HULLS & 30 SX CMT WITH 3% CC. TAG TOC @ 4275'. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT WITH 3% CC WITH 100# HULLS. 2ND PLUG AT 290' WITH 50 SX CMT WITH 3% CC & 100# HULLS. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4520	4530		
4413	4417		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Stephen J Pfeifer  
(TECHNICIAN)

RECEIVED  
AUG - 6 2010  
KCC DODGE CITY

RECEIVED  
AUG 12 2010  
KCC WICHITA

Form EP-278