

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-25413-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 31-18S-11W  
330 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: KIMPLER Well #: 1  
County: BARTON Total Vertical Depth: 3471 feet

Operator License No.: 30458  
Op Name: RJM COMPANY  
Address: PO BOX 256  
CLAFLIN, KS 67525

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF   | 8.625 | 265        | 0           | 180 SX   |
| PROD   | 5.5   | 3464       | 1488        | 180 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/18/2010 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: CHRIS HOFFMAN Company: RJM COMPANY Phone: (620) 587-3600

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/18/2010 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement. Shot off casing at 1488'.  
Pulled to 1400' - pumped 140 sxs cement with 300# hulls.  
Pulled to 600' - pumped 25 sxs cement with 100# hulls.  
Pulled to 303' - circulated to surface with 135 sxs cement with 100# hulls.  
Pulled casing - hole stayed full.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3432 | 3436 |      |          |
| 3418 | 3420 |      |          |
| 3411 | 3413 |      |          |
| 3401 | 3403 |      |          |

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #36395.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

RECEIVED

Form CP-2/3

NOV 01 2010

KCC WICHITA

OCT 26 2010