

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-30187-00-01 ;
Spot: E2NESW Sec/Twnshp/Rge: 12-10S-26W
1999 feet from S Section Line, 3108 feet from E Section Line
Lease Name: FLAGLER Well #: 1
County: SHERIDAN Total Vertical Depth: 4098 feet

Operator License No.: 33268
Op Name: RL INVESTMENT, LLC
Address: 217 SAINT PETER ST
MORLAND, KS 67650

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	226	0	w/175 sxs cmt
PROD	5.5	4098	0	w/175 sxs cmt

Well Type: EOR UIC Docket No: E25535.1 Date/Time to Plug: 10/19/2010 11:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: LEON PFEIFER Company: RL INVESTMENT, LLC Phone: (785) 627-5711

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 10 sxs gel - 600# hulls.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/19/2010 5:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface pipe set at 226' w/175 sxs cement.
5 1/2" production casing set at 4098' w/175 sxs cement.
5 1/2" casing was perforated at 2000' - squeezed with 400 sxs.
CIBP set at 3950'.
Ran tubing to 3710' - pumped 10 sxs gel followed with 60 sxs cement and 200# hulls.
Pulled tubing to 2260' - pumped 110 sxs cement with 100# hulls.
Pulled tubing to 1200' - pumped 160 sxs cement.
Pulled tubing to surface.
Connected to 5 1/2" production casing - pumped 25 sxs cement.
Excavated 8 5/8" surface casing - cement visible in annulus.

Perfs:

Top	Bot	Thru	Comments
3846	4036		

Remarks: S.O.S. CEMENTING COMPANY-TICKET #468.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

RECEIVED
NOV 01 2010^{om} CP-2/3
KCC WICHITA

OCT 21 2010