

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-31460-00-00
Spot: SESWSE Sec/Twnshp/Rge: 19-23S-14W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: KACHELMAN Well #: 1
County: STAFFORD Total Vertical Depth: 3850 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3763		
SURF	8.625	247		WITH 175 SX CMT
PROD	5.5	3849	2028	WITH 120 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/24/2010 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAIME HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3680' WITH 5 SX CMT. PLUG AT 930' WITH 15 SX GEL, 200# HULLS, & 50 SX CMT. PLUG AT 270' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/24/2010 3:08 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3672' & 5 SX CMT WITH A DUMP BAILER. 1ST PLUG AT 934' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 275' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3728	3733		LANSING KC

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
JUN 25 2010
KCC DODGE CITY

RECEIVED
JUL 14 2010
KCC WICHITA

Form CP 2/3