

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-21327-00-00
Spot: E2NWSE Sec/Twnshp/Rge: 32-18S-1E
1990 feet from S Section Line, 1715 feet from E Section Line
Lease Name: BCW FARMS Well #: 2
County: MARION Total Vertical Depth: 2883 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 125 N MARKET ST STE 1120
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	250		140 SX
T1	2.375	2865		
PROD	4.5	2882	1407	185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2010 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: ALAN NATION Company: _____ Phone: (620) 222-4304

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 09/20/2010 4:25 PM KCC Agent: SHANE JONES

Actual Plugging Report:

MIKE'S LAID OUT THE WELL AND DROPPED SAND. THEY TAGGED SAND @ 2783' AND CAPPED W/4 SXS. THEY SHOT OFF CASING @ 1407' AND LAID IT OUT. THEY THEN RIGGED DOWN AND MOVED OFF. 9/20/2010 COPELAND OUT AND RAN POLY TO 300' AND CIRCULATED 125 SXS OF 60/40 POS W/4% GEL TO SURFACE. (TK #34808). 9/21/2010 I CHECKED TOP PLUG AND FOUND IT DOWN 7'. 9/22/2010 COPELAND OUT TO TOP OFF WELL. RANGE CUT CASING OFF AT SURFACE OF CEMENT APPROX 7' DOWN.

Perfs:

Top	Bot	Thru	Comments
2850	2858	CSG	

Remarks:

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED
OCT 06 2010
KCC WICHITA

Form CP-2/3