

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-115-21314-00-00  
Spot: NESWNE Sec/Twnshp/Rge: 9-19S-1E  
3325 feet from S Section Line, 1756 feet from E Section Line  
Lease Name: SCHLEHUBER Well #: 2  
County: MARION Total Vertical Depth: 2865 feet

Operator License No.: 5120  
Op Name: RANGE OIL COMPANY, INC.  
Address: 125 N MARKET ST STE 1120  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	264		165 SX
T1	2.375	2851		
PROD	4.5	2864	1310	235 SZ

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/20/2010 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: (620) 222-4304

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/22/2010 6:00 PM KCC Agent: SHANE JONES


Actual Plugging Report:  
MIKE'S LAID OUT THE WELL AND DROPPED SAND. THEY TAGGED SAND @ 2755' AND CAPPED W4/SXS. THEY SHOT OFF CASING @ 1310' AND LAID IT OUT. THEY THEN RIGGED DOWN AND MOVED OFF. 9/20/2010 COPELAND OUT AND RAN POLY TO 345' AND CIRCULATED 115 SXS OF 60/40 POS W/4% GEL TO SURFACE (TK #34805). 9/21/2010 I CHECKED TOP PLUG AND FOUND IT DOWN 30'. 9/22/2010 COPELAND OUT AND FOUND A BRIDGE @ 30' TAGGED SOLID @ 65'. THEY TOPPED OFF WELL WITH 30 SXS OF COMMON (TK #34813).

Perfs:

Top	Bot	Thru	Comments
2843	2846	CSG	
2836	2838	CSG	

Remarks:  
Plugged through: TBG

District: 02

Signed  (TECHNICIAN)

RECEIVED  
OCT 06 2010  
KCC WICHITA

✓JK