

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-21352-00-00
Spot: NWSE Sec/Twnshp/Rge: 9-19S-1E
1982 feet from S Section Line, 2020 feet from E Section Line
Lease Name: SCHLEHUBER Well #: 3
County: MARION Total Vertical Depth: 2874 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 125 N MARKET ST STE 1120
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	295		150 SX CMT.
T1	2.375	2869		
PROD	4.5	2874	1375	185 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2010 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: (620) 222-4304

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 09/22/2010 6:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

MIKE'S LAID OUT THE WELL AND DROPPED SAND. THEY TAGGED SAND @ 2775 AND CAPPED W/4 SXS. THEY SHOT OFF CASING @ 1375' AND LAID IT OUT. THEY THEN RIGGED DOWN AND MOVED OFF. 9/20/2010 COPELAND OUT AND RAN POLY TO 345' AND CIRCULATED 130 SXS OF 60/40 POS W/4% GEL TO SURFACE (TK #34806). 9/21/2010 I CHECKED TOP PLUG AND FOUND IT DOWN 30'. 9/22/2010 COPELAND OUT AND TOPPED OFF WELL WITH 25 SXS OF COMMON (TK #34814).

Perfs:


Top	Bot	Thru	Comments
2847	2853	CSG	

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED
OCT 06 2010

Form CP-2/3

KCC WICHITA