

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-22618-00-00  
Spot: SWSE Sec/Twnshp/Rge: 9-24S-5E  
660 feet from S Section Line, 1720 feet from E Section Line  
Lease Name: WALTERS B Well #: 16  
County: BUTLER Total Vertical Depth: 2640 feet

Operator License No.: 5120  
Op Name: RANGE OIL COMPANY, INC.  
Address: 125 N MARKET ST STE 1120  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	219		
PROD	4.5	2638		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/28/2010 8:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: ALAN NATION Company: RANGE OIL CO Phone: (316) 265-6231

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE  
Date/Time Plugging Completed: 06/29/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

A FREE POINT TEST FOUND THE 2-3/8" TBG WAS HUNG UP @ 2100'. LOG TECH CUT TBG @ 2052', CONSOLIDATED ESTABLISHED CIRCULATION & PUMPED 32 SXS CLASS A COMMON 3% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 1960'. SHOT SQUEEZE HOLES @ 250'. CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION & PUMPED 105 SXS 60/40 POZMIX 45 GEL TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET #28483.

Perfs:

Top	Bot	Thru	Comments
2524	2526	CSG	

RECEIVED  
NOV 02 2010  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger  
(TECHNICIAN)