

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21653-00-00
Spot: SWNENESW Sec/Twnshp/Rge: 18-24S-24W
2136 feet from S Section Line, 2036 feet from W Section Line
Lease Name: WILSON Well #: 18-11
County: HODGEMAN Total Vertical Depth: 6000 feet

Operator License No.: 32204
Op Name: REDLAND RESOURCES, INC.
Address: 6001 NW 23RD ST
OKLAHOMA CITY, OK 73127

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	961		WITH 350 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/29/2010 3:15 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: DAVID HICKMAN Company: REDLAND RESOURCES Phone: (405) 789-7104

Proposed Plugging Method: 1ST PLUG AT 5478' WITH 50 SX CMT. 2ND PLUG AT 1740' WITH 50 SX CMT. 3RD PLUG AT 990' WITH 50 SX CMT. 4TH PLUG AT 210' WITH 30 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: NONE
Date/Time Plugging Completed: 07/29/2010 5:15 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

Perfs:

1ST PLUG AT 5479' WITH 50 SX CMT. 2ND PLUG AT 1731' WITH 50 SX CMT. 3RD PLUG AT 977' WITH 50 SX CMT. 4TH PLUG AT 221' WITH 30 SX CMT. 5TH PLUG AT 63' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
AUG - 3 2010
KCC DODGE CITY

Signed

Jerry W. Stapleton
(TECHNICIAN)
PART II

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-273
AUG 09 2010
CONSERVATION DIVISION
WICHITA, KS