

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21385-00-01
Spot: SESENE Sec/Twnshp/Rge: 3-23S-31W
2260 feet from N Section Line, 380 feet from E Section Line
Lease Name: TRANS AM S Well #: 1-3
County: FINNEY Total Vertical Depth: 4920 feet

Operator License No.: 32198
Op Name: PETROSANTANDER (USA) INC.
Address: 6363 WOODWAY DR STE350
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4705		WITH 2 SX CMT
SURF	8.625	472		WITH 290 SX CMT
PC		2060		WITH 350 SX CMT
PROD	5.5	4917	0	WITH 195 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/22/2010 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: RON KROEGER Company: PETROSANTANDER Phone: (620) 275-2388

Proposed Plugging Method: CIBP @ 4700'+/- WITH 2 SX CMT. RUN TBG TO 2100'+/-. LOAD HOLE WITH WATER. SPOT 25 SX CMT AT 2100'. PULL UP TO 1300' & CIRCULATE HOLD FULL OF CMT. TOOH W/TBG. HOOK TO ANNULUS & ATTEMPT TO PUMP IN 50-75 SX CMT IN CASE PRIMARY CMT FELL BACK.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/22/2010 12:15 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4705' WITH 2 SX CMT. 1ST PLUG AT 2115' WITH 25 SX CMT. 2ND PLUG AT 1320' WITH 135 SX CMT. CIRCULATED CMT TO SURFACE. TOOH W/ TBG TO TOP 5 1/2" CASING OFF WITH 30 SX CMT. PUMP 55 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS. PRESSURE TO 400# & HELD.

Perfs:

Top	Bot	Thru	Comments
4843	4846		
4785	4790		
4766	4770		

INVOICED

DATE _____
VV. NO. _____

RECEIVED
JUL 19 2010

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% BY CONSOLIDATED OIL WELL SERVICE.

Plugged through: TBG

District: 01

RECEIVED
JUN 28 2010
KCC DODGE CITY

Signed *Ken Jehlik*
(TECHNICIAN)