

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21508-00-00
Spot: NWSE Sec/Twnshp/Rge: 13-26S-9W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease Name: BETTS Well #: 3
County: RENO Total Vertical Depth: 4172 feet

Operator License No.: 31160
Op Name: PHILLIPS EXPLORATION COMPANY L.
Address: 1601 SAGEBRUSH
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3512		
CIBP		3754		
SURF	8.625	265		275 SX CMT.
T1	2.375	4142		
PROD	5.5	4142		200 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKERSON Company: D S & W WELL SERVICE Phone: (620) 793-5838

Proposed Plugging Method: AS PER KCC RULES

Plugging Proposal Received By: DAVID BOLLENBACK Witness Type: PARTIAL
Date/Time Plugging Completed: 07/02/2010 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

7/2/2010 - CIBP @ 3512'. SANDED BACK TO 2980' BAILED 5 SXS ON TOP OF SAND. SHOT CASING OFF AT 1698', PULLED CASING TO 1280' SPOTTED 35 SXS OF CEMENT, PULLED CASING TO 760' SPOTTED 35 SXS OF CEMENT, PULLED CASING TO 302' CIRCULATED TO SURFACE WITH 80' SXS OF CEMENT. 7/12/2010 - FELL BACK 90' - TOPPED WITH 25 SXS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3886	3898	CSG	
3648	3654	CSG	
3369	3372	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 09 2010

INVOICE CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING OUT OF GREAT BEND -- TICKET #36715 DATE _____
Plugged through: CSG INV. NO. _____

District: 02

Signed Bj Hope
(TECHNICIAN)