

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-02070-00-017
Spot: SWSWNW Sec/Twnshp/Rge: 29-22S-11W
2968 feet from S Section Line, 4908 feet from E Section Line
Lease Name: SPANGENBERG W Well #: 2
County: STAFFORD Total Vertical Depth: 3604 feet

Operator License No.: 32432
Op Name: LA VETA OIL & GAS, LLC
Address: 312 N. BUFFALO
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2700		WITH 2 SX CMT
SURF	13	236		WITH 225 SX CMT
L1		3553		3553-3593
PROD	6	3560	0	WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/19/2010 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/19/2010 11:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3400' & PUT 6 SX CMT ON TOP OF SAND BRIDGE. SET CIBP @ 2700' & PUT 2 SX CMT ON TOP OF CIBP. RAN BOND LOG. FOUND GOOD CMT FROM 430' TO 390'. (WELL HAD PREVIOUSLY BEEN SQUEEZED FROM 183'-473' DUE TO CASING LEAKS). PERFORATE 6" CASING @ 600' & RUN 1" PIPE TO 295' IN 13" X 6" ANNULUS. PUMPED DOWN 1" TBG WITH 210 SX CMT. CMT DID CIRCULATE UP 13" X 6" ANNULUS. LAID DOWN 1" TBG. RUN IN 6" CASING WITH 600' OF 2 3/8" TBG. CIRCULATED 6" CASING WITH 85 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3593	3604	OH	
3579	3586	OH	
2759	2764		

INVOICED

DATE _____
INV. NO. _____

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

RECEIVED

AUG 30 2010

KCC DODGE CITY

Signed

Stephen J. Pfeifer

(TECHNICIAN)

RECEIVED

SEP 07 2010

KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form KSONA-1
July 2010
Form Must Be Typed
Form must be Signed
All blanks must be Filled

**CERTIFICATION OF COMPLIANCE WITH THE
KANSAS SURFACE OWNER NOTIFICATION ACT**

This form must be submitted with all Forms C-1 (Notice of Intent to Drill); CB-1 (Cathodic Protection Borehole Intent); T-1 (Request for Change of Operator Transfer of Injection or Surface Pit Permit); and CP-1 (Well Plugging Application). Any such form submitted without an accompanying Form KSONA-1 will be returned.

Select the corresponding form being filed: C-1 (Intent) CB-1 (Cathodic Protection Borehole Intent) T-1 (Transfer) CP-1 (Plugging Application)

OPERATOR: License # 32432
Name: LaVeta Oil & Gas
Address 1: P.O. Box 780
Address 2: _____
City: Middleburg State: VA Zip: 20118 + _____
Contact Person: Martin Ziegler
Phone: (620) 546-4559 Fax: (_____) _____
Email Address: ziegleredna@sbcglobal.net

Well Location:
____ SW ____ SW ____ NW Sec. 29 Twp. 22 S. R. 11 East West
County: Stafford
Lease Name: Wm Spangenberg Well #: 2

If filing a Form T-1 for multiple wells on a lease, enter the legal description of the lease below:

Surface Owner Information:

Name: Virgil Gatton
Address 1: 1105 NE 110th Avenue
Address 2: _____
City: Stafford State: KS Zip: 67578 + _____

When filing a Form T-1 involving multiple surface owners, attach an additional sheet listing all of the information to the left for each surface owner. Surface owner information can be found in the records of the register of deeds for the county, and in the real estate property tax records of the county treasurer.

If this form is being submitted with a Form C-1 (Intent) or CB-1 (Cathodic Protection Borehole Intent), you must supply the surface owners and the KCC with a plat showing the predicted locations of lease roads, tank batteries, pipelines, and electrical lines. The locations shown on the plat are preliminary non-binding estimates. The locations may be entered on the Form C-1 plat, Form CB-1 plat, or a separate plat may be submitted.

Select one of the following:

- I certify that, pursuant to the Kansas Surface Owner Notice Act (House Bill 2032), I have provided the following to the surface owner(s) of the land upon which the subject well is or will be located: 1) a copy of the Form C-1, Form CB-1, Form T-1, or Form CP-1 that I am filing in connection with this form; 2) if the form being filed is a Form C-1 or Form CB-1, the plat(s) required by this form; and 3) my operator name, address, phone number, fax, and email address.
- I have not provided this information to the surface owner(s). I acknowledge that, because I have not provided this information, the KCC will be required to send this information to the surface owner(s). To mitigate the additional cost of the KCC performing this task, I acknowledge that I am being charged a \$30.00 handling fee, payable to the KCC, which is enclosed with this form.

If choosing the second option, submit payment of the \$30.00 handling fee with this form. If the fee is not received with this form, the KSONA-1 form and the associated Form C-1, Form CB-1, Form T-1, or Form CP-1 will be returned.

I hereby certify that the statements made herein are true and correct to the best of my knowledge and belief.

Date: 8-16-10 Signature of Operator or Agent: Marty Ziegler Title: Contact Agent

RECEIVED

SEP 07 2010