

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-193-20779-00-00  
Spot: SENENWSE Sec/Twnshp/Rge: 21-10S-31W  
2290 feet from S Section Line, 1470 feet from E Section Line  
Lease Name: OTTLEY Well #: 21-1  
County: THOMAS Total Vertical Depth: 4050 feet

Operator License No.: 34315  
Op Name: KANSAS OIL RESOURCES LLC  
Address: 11944 W 95TH ST, STE 222  
SHAWNEE MISSION, KS 66216

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF   | 8.625 | 237        |             |          |

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/27/2010 1:00 PM  
Plug Co. License No.: 34432 Plug Co. Name: FALCON DRILLING, LLC  
Proposal Rcvd. from: \_\_\_\_\_ Company: KANSAS OIL RESOURCES LLC Phone: (816) 210-8926

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB WitnessType: NONE  
Date/Time Plugging Completed: 09/27/2010 3:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 2555' w/25 sxs.  
2nd. Plug at 1233' w/100 sxs.  
3rd. Plug at 287' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.

Perfs:

**INVOICED**

DATE \_\_\_\_\_  
INV. NO. \_\_\_\_\_

Remarks: CONSOLIDATED CEMENTING COMPANY.

Plugged through: DP

RECEIVED  
OCT 07 2010  
KCC WICHITA

District: 04

Signed [Signature] 10/4/2010  
(TECHNICIAN)

CM

OCT 04 2010