

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-079-00739-00-00  
Spot: SWSENENW Sec/Twnshp/Rge: 6-23S-3W  
4026 feet from S Section Line, 3102 feet from E Section Line  
Lease Name: FREDERICK Well #: 13  
County: HARVEY Total Vertical Depth: 3345 feet

Operator License No.: 7116  
Op Name: KANTOR OIL COMPANY, LLC  
Address: 15 W 6TH ST STE 2601  
TULSA, OK 74119

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	323		
PROD	5.5	3333		75 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.  
Proposal Rcvd. from: LARRY RESSLER Company: KANTOR OIL CO Phone: (620) 664-0597

Proposed Plugging Method: PER KCC RULES

Plugging Proposal Received By: SHANE JONES Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/14/2010 2:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CASING WAS COLLAPSED AT 1800', 9/13/2010 RAN TUBING INTO 1760' SPOTTED 100 SX COMMON CEMENT W/3% CC, TAGGED CEMENT @ 1400'. PULLED TUBING TO 619' SPOTTED 45 SXS OF CEMENT, PULLED TO 375' PUMPED 135 SXS OF CEMENT DID NOT CIRCULATE. 9/14/2010 CUT HEAD OFF, TAGGED CEMENT INSIDE 5.5 AT 45', TAGGED CEMENT BETWEEN 5.5" AND 8.625 @ 120', RAN 1 INCH IN AND RAISED CEMENT TO SURFACE WITH 25 SXS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3333	3345	OH	

INVOICED

DATE \_\_\_\_\_

INV. NO. \_\_\_\_\_

RECEIVED

NOV 02 2010


KCC WICHITA

Remarks: COPELAND CEMENT OUT OF BURRTON TICKET #34697

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)