

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21965-00-00
Spot: NENESW Sec/Twnshp/Rge: 20-9S-22W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: FARRELL Well #: 4
County: GRAHAM Total Vertical Depth: 3993 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 1700 N WATERFRONT PKY BLDG 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	257	0	160 SX
PROD	4.5	3995	0	600 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/23/2010 8:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: EARL KNIGHTON Company: KNIGHTON OIL COMPANY, INC. Phone: (316) 630-9905

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 300# hulls.
Tubing and rods stuck in the hole at 2042'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/23/2010 11:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2036' - pumped 100 sxs 60/40 pozmix - 4% gel with 100# hulls.
Pulled tubing to 995' - pumped 120 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.
Pulled all tubing. Topped off 4 1/2" casing with 25 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 4 1/2" annulus. Pumped 5 sxs 60/40 pozmix - 4% gel.
S.I.P. 275#.

Perfs:

Top	Bot	Thru	Comments
3884	3888		LANSING
3859	3863		LANSING
3837	3840		LANSING
3824	3827		LANSING
3801	3804		LANSING
3762	3766		LANSING
3752	3757		LANSING
3740	3742		LANSING
3718	3724		LANSING
3704	3710		LANSING
3675	3682		LANSING
3667	3672		LANSING

INVOICED

DATE _____
INV. NO. _____

RECEIVED

SEP 03 2010

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #41926.

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN)

CM

BROUGHER OIL, INC.

P. O. DRAWER 1367
GREAT BEND, KS 67530

#4 FARRELL

20-9-22W
NE NE SW

CONTR JOHN O. FARMER, INC.

CTY GRAHAM


GEOL

FIELD RED LINE NW

ELV 2424 KB SPD 4/25/84
2419 GL

CARD ISSUED 7/21/84

IP P 40 BO & 40 BWPD
LKC 3667-3888



LOG	Tops	Depth/Datum
ANH	1955+ 469
TOP	3413- 989
HEEB	3631-1207
TOR	3653-1229
LKC	3667-1243
BKC	3894-1470
MARM	3964-1540
RTD	3993-1569

API 15-065-21,965

8 5/8 " 257 / 160SX, 4 1/2 " 3995 / 600SX

DST (1) 3659-3702 (LKC) / 60-30-60-30, 372' GIP, REC 62' MCO, 124' OCM, 62' OCW, SIP 653-595#, FP 39-98 / 108-147#

DST (2) 3691-3723 (LKC) / 30-30-60-45, 435' GIP, REC 248' OCM, 62' VSOCM, SIP 420-400#, FP 28-98 / 108-176#

DST (3) 3730-3777 (LKC) / TIMES NA, REC 372' SL OIL SPTD MUD, SIP 332-332#, FP 39-78 / 166-205#

DST (4) 3780-3872 (LKC) / 120-45-60-70, REC 186' SOCM, SIP 283-342#, FP 68-108 / 108-127#

MICT - CO, PF (LKC) 3884-88, 3859-63, W/3 SPF, AC 3000G (15% NECRA) & 200# TLC & 200# ROCK SALT, SWB DWN, SO, PF (LKC) 3801-04, 3824-27, 3837-40, W/3 SPF, AC 4000G (15% NECRA), SWB DWN, SO, PF (LKC) 3762-66, 3752-57, 3740-42, W/3 SPF, AC 3500G (15% NECRA), SWB DWN, SO, PF (LKC) 3718-24, 3704-10, W/3 SPF, AC 3000G (15% NECRA), SWB DWN, SO, PF (LKC) 3667-72, 3675-82, W/3 SPF, AC 3000G (15% NECRA), SWB DWN, SO, POP, P 40 BO & 40 BWPD, 6/21/84

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS