

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23706-00-00
Spot: SESWSWNE Sec/Twnshp/Rge: 29-18S-11W
2858 feet from S Section Line, 2210 feet from E Section Line
Lease Name: KLEEPER Well #: 1
County: BARTON Total Vertical Depth: 3500 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	333	0	225 SX
PROD	5.5	3499	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/28/2010 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel - 400# hulls - 12 sxs gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/28/2010 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3000' - pumped 12 sxs gel - followed with 25 sxs cement.
Pulled tubing to 1500' - pumped 90 sxs cement with 300# hulls.
Pulled tubing to 660' - circulated to surface with 55 sxs cement.
Pulled tubing - topped off with 5 sxs cement.
Surface pipe had been orange peeled - cut open pipe - full cement.

Perfs:

Top	Bot	Thru	Comments
3420	3425		
3413	3413		
3408	3408		

INVOICED

DATE _____

INV. NO _____

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #35121.

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

CM

RECEIVED

OCT 04 2010
10-28-10

Form CP-2/3

OCT 04 2010