

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24125-00-00
Spot: SENESWSW Sec/Twnshp/Rge: 13-20S-12W
735 feet from S Section Line, 1020 feet from W Section Line
Lease Name: MARCHAND Well #: 1
County: BARTON Total Vertical Depth: 3407 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	261	0	225 SX
PROD	5.5	3404	2250	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/29/2010 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/29/2010 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement.
Cut casing at 2250' - pulled to 1500' - pumped 175 sxs cement with 200# hulls.
Pulled casing to 600' - pumped 25 sxs cement.
Pulled casing to 300' - circulated cement to surface with 150 sxs cement and 100# hulls.
Pulled casing - topped off with 20 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3361	3363		ARBUCKLE
3348	3352		ARBUCKLE

INVOICED

DATE: _____
INV. NO. _____

RECEIVED

OCT 18 2010

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #35124.

Plugged through: CSG

KCC WICHITA

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

Form CP-2/3

OCT 13 2010