

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-20274-00-00
Spot: NENESW Sec/Twnshp/Rge: 18-16S-1W
2377 feet from S Section Line, 2981 feet from E Section Line
Lease Name: PASSMORE Well #: 1
County: SALINE Total Vertical Depth: 2688 feet

Operator License No.: 31434
Op Name: L & J OIL PROPERTIES, INC.
Address: 635 N STRATFORD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	210		130 SX
PROD	4.5	2688	1400	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/08/2010 11:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIS Company: _____ Phone: (620) 628-4723

Proposed Plugging Method: AS PER KCC REGULATIONS


Plugging Proposal Received By: _____ Witness Type: NONE
Date/Time Plugging Completed: 09/08/2010 1:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:
9/7/2010 SUNFLOWER LAID OUT WELL AND DROPPED SAND. 9/8/2010 SUNFLOWER TAGGED SAND AROUND 2630' AND CAPPED W/4 SXS. SUNFLOWER THEN TIED ON CASING AND RIPPED IT "@ 1400'. SUNFLOWER LAID OUT THE CASING. THE RAN BAILER IN AND FOUND FLUID @ 400' THEY DECIDED TO SLURRY PLUG THE TOP FROM 400' TO SURFACE. THEY USED 7YDS OF SLURRY FROM SMOKY VALLEY CONCRETE OF SALINA TK #027432. 9/9/2010 I CHECKED TOP PLUG. I FOUND IT HAD FALLEED APPROX 30'. I NOTIFIED BUD DAVIS W/SUNFLOWER WELL SERVICE. BUD SAID HE WOULD GET IT TAKEN CARE OF ONCE IT DRIED UP AGAIN.

Perfs:
INVOICED
DATE _____
INV. NO. _____

Remarks: WELL HAD A DENIED TA WITH A DEADLINE DATE OF 4/28/2008??
Plugged through: CSG

District: 02

Signed  (TECHNICIAN)

RECEIVED
Form CP-2/3
SEP 15 2010
KCC WICHITA

JK