

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22339-00-00
Spot: NESWNENE Sec/Twnshp/Rge: 3-26S-15W
4417 feet from S Section Line, 771 feet from E Section Line
Lease Name: GILES Well #: 1
County: PRATT Total Vertical Depth: 4500 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	388		WITH 375 SX CMT
PROD	4.5	4495	1728	WITH 375 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/14/2010 10:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TOM DICKSON Company: D S & W WELL SERVICING, INC. Phone: (620) 793-5838

Proposed Plugging Method: SAND TO 3850' WITH 4 SX CMT. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/14/2010 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 3850' & PUT 4 SX CMT ON TOP OF SAND BRIDGE. 1ST PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3898	3904		

INVOICED
DATE _____
INV. NO. _____

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Steve Pfeifer
(TECHNICIAN)

RECEIVED
OCT 22 2010
KCC DODGE CITY

RECEIVED
OCT 27 2010
KCC WICHITA

Form CP 2/3