

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-22347-00-00  
Spot: NWNW Sec/Twnshp/Rge: 34-29S-11W  
4610 feet from S Section Line, 4656 feet from E Section Line  
Lease Name: POLAND Well #: 1-34  
County: PRATT Total Vertical Depth: 4800 feet

Operator License No.: 6039  
Op Name: L.D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	394		WITH 400 SX CMT
PROD	4.5	2956	2100	WITH 150 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/08/2010 11:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK TO 50' ABOVE PERFS & 4 SX CMT. PLUG AT 720' WITH 15 SX GEL & 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: NONE  
Date/Time Plugging Completed: 10/11/2010 9:45 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SANDED BACK TO 2718' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 720' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 430' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2768	2774		INDIAN CAVE

**INVOICED**  
DATE \_\_\_\_\_  
INV. NO. \_\_\_\_\_  
**RECEIVED**  
**OCT 15 2010**  
**KCC WICHITA**

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

**RECEIVED**  
OCT 13 2010  
KCC DODGE CITY

Signed \_\_\_\_\_

Jerry W. Stapleton  
(TECHNICIAN)  
PART II

Form CP 2/3