

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22675-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 12-22S-12W
1694 feet from S Section Line, 2320 feet from E Section Line
Lease Name: WILLINGER Well #: 5
County: STAFFORD Total Vertical Depth: 3920 feet

Operator License No.: 32432
Op Name: LA VETA OIL & GAS, LLC
Address: 312 N. BUFFALO
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	301		WITH 250 SX CMT
PROD	5.5	3920	1015	WITH 275 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/20/2010 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 3530' & PUT 5 SX CMT ON TOP OF SAND BRIDGE. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/20/2010 1:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 3600'. SAND BACK TO 3530' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3584	3592		

INVOICED
DATE _____
INV. NO. _____

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed _____

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
AUG 30 2010
KCC DODGE CITY

RECEIVED
SEP 07 2010
KCC WICHITA

FORM CP-273