

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20766-00-00  
Spot: SWNE Sec/Twnshp/Rge: 35-18S-34W  
2310 feet from N Section Line, 1550 feet from E Section Line  
Lease Name: WILLIAMS Well #: 1-35  
County: SCOTT Total Vertical Depth: 5000 feet

Operator License No.: 5214  
Op Name: LARIO OIL & GAS COMPANY  
Address: 301 S MARKET ST  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	379		WITH 220 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/14/2010 8:00 PM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: KIRBY STRUTT Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2380' WITH 50 SX CMT. 2ND PLUG AT 1330' WITH 80 SX CMT. 3RD PLUG AT 660' WITH 50 SX CMT. 4TH PLUG AT 400' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE  
Date/Time Plugging Completed: 08/14/2010 10:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

1ST PLUG AT 2380' WITH 50 SX CMT. 2ND PLUG AT 1330' WITH 80 SX CMT. 3RD PLUG AT 660' WITH 50 SX CMT. 4TH PLUG AT 400' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

INVOICED

DATE \_\_\_\_\_  
INV. NO. \_\_\_\_\_

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

RECEIVED  
SEP 11 2010  
9-1-10  
KCC WICHITA

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
AUG 17 2010  
KCC DODGE CITY

Form CP3263