

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20819-00-00
Spot: NESENE Sec/Twnshp/Rge: 24-7S-20W
3630 feet from S Section Line, 330 feet from E Section Line
Lease Name: CARLSON Well #: 1
County: ROOKS Total Vertical Depth: 3499 feet

Operator License No.: 8925
Op Name: LIBERTY OPER & COMPL, INC
Address: 308 W MILL
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	199	0	140 SX
PROD	5.5	3500	0	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/17/2010 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ROGER COMEAU Company: LIBERTY OPER & COMPL, INC Phone: (785) 434-4686

Proposed Plugging Method: Ordered 100 sxs 60/40 pozmix - 4% gel.
2 7/8" tubing cemented in with 100 sxs.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/17/2010 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran 1" tubing to 2975 - pumped 25 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 1975' - pumped 25 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 975' - pumped 23 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing. Squeezed in 7 sxs 60/40 pozmix - 4% gel. S.I.P. 100#.
Hooked to 5 1/2" casing. Squeezed in 5 sxs 60/40 pozmix - 4% gel. S.I.P. 1000#.
8 5/8" x 5 1/2" annulus. Pressured to 300# immediately.

Perfs:

Top	Bot	Thru	Comments
3468	3476		

INVOICED
DATE _____
INV. NO. _____

Remarks: ALLIED CEMENTING COMPANY-TICKET #41746.

Plugged through: TBG

RECEIVED
AUG 23 2010
KCC WICHITA

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

AUG 19 2010

LIBERTY ENTERPRISES, INC. #1 CARLSON 24-7-20W
 308 W. MILL PLAINVILLE, KS. 67663 NE SE NE
 CONTR PIONEER DRILG. CO., INC. CTV ROOKS

GEOL CHARLES G. COMEAU FIELD VALLEY VIEW EXT (1/8 W)

E 2012 KB CM 6/5/78 CARD ISSUED 7/27/78 P 15 BO + 2 BWPD
 ARB 3468-76

+	+	+
+	+	+
+	+	+

API 15-163-20,819

SMP	TOPS	DEPTH	DATUM
ANH	1541	+ 471	
TOP	2971	- 959	
HEEB	3170	-1158	
TOR	3195	-1183	
LKC	3211	-1199	
BKC	3418	-1406	
ARB	3462	-1450	
RTD	3500	-1488	

8-5/8" 199/140sx, 5 1/2" 3500/100sx
 DST (1) 3118-76/30-60-60-30, 360' MW,
 SIP 1188-1130#, FP 57-97#, 122-
 219#, HP 1682-1670#
 DST (2) 3442-68/30-30-90-30, 35' GIP,
 20' CL O, 90' OCM, SIP 527-260#,
 FP 37-32#, 36-48#, HP 1832-1805#
 DST (3) 3442-73/30-30-60-30, 135' GIP,
 45' CL O, 120' MO, SIP 551-487#,
 FP 48-64#, 81-105#, HP 1890-1871#
 MICT - CO, PF 32/3468-3476, OIL NAT,
 SWB .75 BOPH, NAT, AC 500 MOD, SWB 1
 BOPH, TR WTR, R&T, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS