

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21668-00-00
Spot: SESESW Sec/Twnshp/Rge: 24-7S-18W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: RUPP Well #: 1
County: ROOKS Total Vertical Depth: 3330 feet

Operator License No.: 8925
Op Name: LIBERTY OPER & COMPL, INC
Address: 308 W MILL
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1199	0	350 SX
PROD	5.5	3300	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/21/2010 1:30 PM
Plug Co. License No.: 33868 Plug Co. Name: RENEGADE WELL SERVICE LLC
Proposal Rcvd. from: ROGER COMEAU Company: LIBERTY OPER & COMPL, INC. Phone: (785) 434-4686

Proposed	Ordered 100 sxs common cement - 3% c.c.
Plugging	Ordered 500 sxs 60/40 pozmix - 4% gel - 300# hulls.
Method:	Perforated at 1150'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/22/2010 4:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

09/21/2010 - Ran tubing to 2800' - pumped 100 sxs common cement with 3% c.c. - no lifting pressure.
Operator is going to pull 1,000' tubing.
Ran tubing back in the morning and tagged cement.
09/22/2010 - Tagged cement at 2860'.
Ran tubing to 2850' - pumped 170 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 1200' - pumped 155 sxs 60/40 pozmix - 4% gel - circulated to surface.
Pulled all tubing. Hooked to 5 1/2" casing - pumped 150 sxs 60/40 pozmix - 4% gel to circulate around 8 5/8" x 5 1/2" annulus.
Shut annulus and pressured to 400#.

Perfs:

Top	Bot	Thru	Comments
3234	3242		
3130	3133		
3032	3035		
2935	2938		
2711	2715		

INVOICED
DATE _____
INV. NO. _____

Remarks: ALLIED CEMENTING COMPANY-TICKET #35465 AND #41990.

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN) CM

RECEIVED
OCT 04 2010
KCC WICHITA
Form CP-2/3

SEP 29 2010