

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24082-00-00  
Spot: NWNW Sec/Twnshp/Rge: 9-19S-25W  
4606 feet from S Section Line, 4635 feet from E Section Line  
Lease Name: HARPER C Well #: 1-9  
County: NESS Total Vertical Depth: 4504 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E CENTRAL STE 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	204		WITH 150 SX CMT
PC		1839		WITH 450 SX CMT
PROD	5.5	4490	0	WITH 100 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/12/2010 8:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVE OLLER Company: QUALITY WELL SERVICE, INC. Phone: (620) 532-9232

Proposed Plugging Method: PUMP 25 SX CMT & 200# HULLS, THEN GEL SPACER TO 1800' THEN CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/12/2010 11:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 25 SX CMT & 200# HULLS, THEN 15 SX GEL & 205 SX CMT. CMT TO SURFACE. MAXIMUM PRESSURE 1750#. SHUT IN PRESSURE 1750#. BACKSIDE 2" CONNECTIONS WAS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4490	4503	OH	OH MISSISSIPPI
1100			

INVOICED

DATE \_\_\_\_\_  
INV. NO. \_\_\_\_\_

RECEIVED

OCT 07 2010

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

RECEIVED

SEP 29 2010

KCC DODGE CITY

Signed

Michael J. Maier  
(TECHNICIAN)

Form CP-243