

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-21281-00-00
Spot: W2SWSW Sec/Twnshp/Rge: 16-21S-35W
677 feet from S Section Line, 4996 feet from E Section Line
Lease Name: CAMPBELL A Well #: 2-16
County: KEARNY Total Vertical Depth: 5000 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	414		WITH 300 SX CMT
DVT		1772		
PROD	4.5	4995	0	WITH 495 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/12/2010 6:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: RUN TBG TO DV TOOL & FILL 4 1/2" WITH CMT TO 0'.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/12/2010 8:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

**DV TOOL @ 1772' WITH 270 SX CMT. RAN 1" TO 875' WITH 120 SX CMT. ** 1ST PLUG PUMP 200# HULLS & 40 SX CMT TO 4493'. 2ND PLUG PUMP 30 BBL GEL SPACER & 130 SX CMT FROM 1800' TO 0'. MAXIMUM PRESSURE 1000#. SHUT IN PRESSURE 500#. 3RD PLUG PUMP 5 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4489	4493		MARMATON

INVOICED
DATE _____
INVOICE NO. _____
RECEIVED
SEP 10 2010

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed _____

Ken Jehlik
(TECHNICIAN)

RECEIVED

AUG 31 2010

KCC DODGE CITY

Form KCC 2/03