

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-20641-00-00  
Spot: E2SWNW Sec/Twnshp/Rge: 11-11S-34W  
3300 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: BERTRAND TRUST A Well #: 1-11  
County: LOGAN Total Vertical Depth: 4800 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E CENTRAL STE 300  
WICHITA, KS 67206

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| CIBP   |       | 4300       |             |          |
| SURF   | 8.625 | 254        | 0           | 170 SX   |
| PROD   | 4.5   | 4786       | 0           | 225 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/12/2010 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVE OLLER Company: MCCOY PETROLEUM CORPORATI Phone: (620) 532-9232

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 300# hulls.  
Top down plug.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/12/2010 3:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 254' w/170 sxs cement.  
4 1/2" production casing set at 4786' w/225 sxs cement.  
Port collar cemented with 400 sxs cement. CIBP at 4300'. PBTD 4740'.  
Connected to 4 1/2" production casing - pumped 50 sxs cement mixed with 200# hulls.  
Pumped 4 sxs gel - followed with 150 sxs cement mixed with 100# hulls.  
Max. P.S.I 1200#. S.I.P. 1200#.  
Connected to 8 5/8" surface casing - pumped 10 sxs cement.  
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4042 | 4052 |      |          |
| 4012 | 4024 |      |          |

**INVOICED**  
DATE \_\_\_\_\_  
INV. NO. \_\_\_\_\_

**RECEIVED**

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKE #5064.

Plugged through: CSG

SEP 03 2010  
9-3-10  
KCC WICHITA

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

MCCOY PETROLEUM CORP  
WICHITA KS 67226-4003

WILDCAT

11-11S-34W  
C E/2 SW NW

# 1-11 BERTRAND TRUST A

site: 1/4 N & 2-3/4 W OF MONUMENT KS      city: LOGAN      API 15-109-20641  
contr: SWEETMAN DRILLING # 2      field: WC (1-1/4 NW OF  
geol: JOHN HASTINGS      MONUMENT WEST)

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

fr date 01/17/97      spd date 03/04/97      drig comp 03/12/97      card issued 03/31/97      last revised 03/31/97

ELV: 3180 EGL  
tops.....depth/datum  
RTD.....4800 -1620  
NO TOPS RPTD

IP status:  
OIL, LKC, INTV NA , 03/25/97  
CSG: 8-5/8" 254 / 170 SX (ALT 2), 4-1/2" 4786  
TRGT ZN: MISS, PTD 4780 (MISS), MICT - CO, PF (KC)  
INTV NA, SO, POP, OIL WELL (POTENTIAL NOT  
RPTD), 3/20/97 - TIGHT HOLE - NO OTHER INFO  
AVAILABLE - TEMP COMP 3/31/97

COPYRIGHT 1997  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS