

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25113-00-00  
Spot: SESESW Sec/Twnshp/Rge: 16-13S-18W  
330 feet from S Section Line, 2740 feet from E Section Line  
Lease/Unit Name: MARVIN Well Number: 1  
County: ELLIS Total Vertical Depth: 3725 feet

Operator License No.: 6412  
Op Name: TOMLINSON, SID  
Address: 424 NORTHWEST 42ND STREET  
OKLAHOMA CITY, OK 73118

Conductor Pipe: Size feet: 8 1/2 1.06  
Surface Casing: Size 8.625 feet: 394  
Production: Size feet:  
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 10/10/2001 8:00 AM

Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.

Proposal Rcvd. from: DORAN MARGHEIM Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed According to KCC Rules & Regulations.  
Plugging Order 175 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Method: Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 10/10/2001 9:30 AM

KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 394'.  
1st. Plug at 3698' w/25 sxs - Arbuckle.  
2nd. Plug at 1470' w/25 sxs - Anhydrite  
3rd. Plug at 750' w/100 sxs - Dakota Base.  
4th. Plug at 40' w/10 sxs - 8 5/8" wiper plug.  
Rathole with 15 sxs.  
Total of 175 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.

Remarks: LEASE READS AS FOLLOWS: 190' N. OF SESESW 16-13-18W. ALLIED CEMENTING COMPANY. HONAS TANK-

Plugged through: DP

District: 04  
**RECEIVED**

Signed Raymond L. Moses  
(TECHNICIAN)

OCT 26 2001  
10-26-01  
KCC WICHITA

OCT 15 2001

**INVOICED**

Form CP-2/3

DATE 10-26-01

INV. NO. 2002060860