

4-6

4-061063

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-24,957-000

W2 W2 NE /4 SEC. 16, 13 S, 18 W
3960 feet from S section line
2310 feet from E section line

Operator license# 8061

Lease Arnold Well # 4

Operator: Oil Producers Inc. Of Kansas

County: Ellis 121.23

Address: P.O. Box 8647
Wichita, Kansas 67208

Well total depth 3730 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 692 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Mallard JV Inc. License# 4958

Address: McPherson, Kansas 67460

Company to plug at: Hour: 4:15 A.M. Day: 6 Month: April Year: 1997

Plugging proposal received from: Lyle Jorgensen

Company: Mallard JV Inc. Phone:

Were: Order 165 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.

RECEIVED
KANSAS CORP COMM
1997 APR 10 A 11:11
4-10-97

Plugging Proposal Received by: Herb Deines/Richard Lacey
Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 8:15 A.M. Day: 6 Month: April Year: 1997

Actual plugging report:
1st. Plug at 1460' w/50 sxs. Anhydrite 1442' - 1482'.
2nd. Plug at 720' w/50 sxs.
3rd. Plug at 350' w/40 sxs.
4th. Plug at 40' w/10 sxs.
15 sxs in rathole.

Remarks: Halliburton Cementing.
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 2160 GL

I did/did not [X] observe the plugging.

Herb Deines (agent)
RH

INVOICED
DATE APR 14 1997
INV. NO. 47914
4-6

JUN 17 1997