

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22600-00-00
Spot: SWSENW Sec/Twnshp/Rge: 16-13S-17W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: DENNIS STAAB Well Number: 1
County: ELLIS Total Vertical Depth: 3650 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252 3706 - 22ND STREET
GREAT BEND, KS 67530

Conductor Pipe: Size feet: 118.63
Surface Casing: Size 8.625 feet: 204 150 SX CMT
Production: Size 4.5 feet: 3649 UNKNOWN
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/10/2002 12:00 PM

Plug Co. License No.: 9090 Plug Co. Name: CHARTER ENERGY, INC.
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY, INC. Phone: (316) 793-9090

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 275 sxs cement and 800# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/10/2002 12:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 204' w/150 sxs. 4 1/2" casing at 3649' w/unknown cement.
No information on ALT II - is known to be two-staged.
Tied to 8 5/8" - squeezed 15 sxs cement with 50# hulls.
Max. P.S.I. 500#. S.I.P. 0#.
Tied to 4 1/2" casing - squeezed 235 sxs cement and 800# hulls.
Max. P.S.I. 200#. S.I.P. 200#.
Total of 250 sxs 60/40 pozmix - 10% gel and 850# hulls.

RECEIVED
1-3-03
JAN 03 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. STEWART TANK-WATER.

Plugged through: CSG

District: 04

Signed

Roger L. Moses
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 1-3-03

WV. NO. 2003061028

DEC 30 2002

ERNST & STEINLE OIL OPERATIONS REPLACEMENT CARD 16-13-17W
 BOX 859 #1 DENNIS STAAB SW SE NW
 RUSSELL, KS 67665--859 (TRACT 34)
 CONTR RANGER DRILLING CTY ELLIS
 GEOL DAVID SHUMAKER FIELD CATHERINE
 ELV 1996 KB SPD 10/22/81 ^{CARD}ISSUED 4/15/82 IP P 12 BOPD, NW
 API 15-051-22,600 ARB OH 3649-3650

+	+	+
+	+	+
+	+	+

SMP	Tops	Depth/Datum
ANH	1256+ 740
TOP	3041-1045
HEEB	3282-1286
TOR	3305-1309
LKC	3328-1332
BKC	3556-1560
ARB	3580-1584
RTD	3650-1654

8 5/8 " 204/150SX; 4 1/2 " 3649
 DST (1) 3552-3605 (ARB) / 45-45-45-45, REC 450' HGCMO (70%
 O, 15% G, 14% W, 1% M), SIP 799-764#, FP 84-108 / 168-
 180#, HP 2011-2000#
 MICT - CO, PF (ARB OH), AC 250G (MA), SWB DWN, POP, P 12
 BOPD - NW, 2/1/82

INFO RELEASED: 3/3/83 - WAS OIL WELL - TIGHT HOLE

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

S211 Section S12