

4-070168

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-22520-0000

NW NE SW /4 SEC. 16, 13 S, 17 W
2310 feet from S section line
3630 feet from E section line

Operator license# 8729

Lease: Leo Walter Well # 1

Operator: Hertel Oil Company

County: Ellis 117.68

Address: 704 E. 12th Street
Hays, Kansas 67601

4/20

Well total depth 3617 RTD - 3621 OH feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 208 feet

ABAND. oil well , Gas well , Input well , SWD. , D&A

Plugging contractor: Hertel Oil Company License# 8729

Address: 704 E. 12th Street - Hays, Kansas 67601

Company to plug at: Hour: 9:30 A.M. Day: 20 Month: April Year: 2000

Plugging proposal received from: Dave Hertel

Company: Hertel Oil Company Phone: 785-628-2445

Were: 4 1/2" casing set at 3617'. Arbuckle open hole completion T.D. 3621'.
Ordered out 250 sxs 60/40 pozmix - 10% gel with 800# hulls.
07-19-95 - Squeezed salt section with 200 sxs. Holes between 1683' and 1715'.
07-21-95 - Squeezed salt section again with 150 sxs.

Plugging Proposal Received by: Rich Williams
Plugging operations attended by agent? All , Part , None

Completed: Hour: 11:00 A.M. Day: 20, Month: April, Year: 2000

Actual plugging report: Maier Well Service ran 2 3/8" tubing to 2500'.
Allied pumped 90 sxs 60/40 pozmix with 300# hulls. Pulled tubing to 1500' and pumped 80 sxs
with 300# hulls - cement circulated. PTOH. Squeezed 25 sxs at Max. P.S.I. 900#.
S.I.P. 300#.

Checked backside pressured to 600#. Cement in cellar.

RECEIVED
STATE CORPORATION COMMISSION

APR 24 2000

4-24-00
CONSERVATION DIVISION
Wichita, Kansas

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 1988 GL

I did / did not observe the plugging.

INVOICE (agent)

DATE 4/25/00

INV. NO. 061639

Form CP-2/3

(R)