

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: State Of Kansas Fee FundName & Linda Drake Lease Project

Address _____

AB oil well _____ Gas Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, IncAddress: 19450 Ford Road, Chanute, Kansas 66720Company to plug at: _____ Hour: _____ Day: 3 Month: 9 2010Plugging proposal received from: Robert KepleyCompany Name: K-W Oil Well Service, Inc Phone: 620-433-7730

Were: Wash well to TD, gel hole and set 50' btm plug, pull pipe to 500' and set 50' plug, pull pipe to 350' and fill to surface with cement.

Plugging Proposal Received by:

Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All _____ Part XXXXXX None _____Operations Completed: Hour: _____ Day: 3 Month: 9 2010Actual Plugging Report: The drill rig was moved to location and the well drilled to 155' thru woodand debris. The rig continued to drill to 850' where the drill string hit iron. The drill string was removed anda 1" cement string washed to 850'. The well was pumped full of cement from btm to top thru this cementstring. A total of 631 sacks of portland cement were used to plug well. The well was cut off below plowdepth and the location restored. Due to nearby active gas wells by "industry", the well was plugged witha continuous cement plug rather than spot plugs.

RECEIVED

FEB 07 2011

Remarks: Control # 20100080-001

(If additional description is necessary, use BACK of this form.)

KCC WICHITA

I partially observed this plugging

Signed:

Alan M. Dunning
TECHNICIAN