

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205- 01016-00-00
NE SW SE Sec/Twp/Rge Sec 6 T30S R15E
725 (gps) feet from south section line
1692 (gps) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Lease/Well# Scott, Lois SCO 01County WilsonOperator: State Of Kansas Fee FundWell Total Depth 1282 feetName & Lois Scott Lease ProjectProduction Pipe: NA Size Feet NA

Address _____

Surface Casing: 12 Size Feet NAAB oil well _____ Gas Well XXXXXX

SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, IncLic. # 3097Address: 19450 Ford Road, Chanute, Kansas 66720Company to plug at: _____ Hour: _____ Day: 21 Month: 9 2010Plugging proposal received from: Robert KepleyCompany Name: K-W Oil Well Service, IncPhone: 620-433-7730

Were: Wash well to TD, gel hole and set 50' btm plug, pull pipe to 500' and set 50' plug, pull pipe to 350' and fill to surface with cement.

Plugging Proposal Received by: _____

Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: _____

All _____

Part _____

XXXXXX

None _____

Operations Completed: Hour: _____

Day: _____

21

Month: _____

9

2010

Actual Plugging Report: _____

The drill rig was moved to location and the well drilled 1305'. The drill pipe was removed and a 1" cement string lowered to 1300'. The well was then circulated clean. A 50' cement plug was then placed at TD. The cement string was raised to 500' and a cement plug spotted. The cement string was then raised to 350' and the well filled to surface. A total of 377 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED

FEB 07 2011

Remarks: Control # 20100081-001

(If additional description is necessary, use BACK of this form.)

KCC WICHITA

I partially observed this plugging

Signed: _____

TECHNICIAN