

To: STATE CORPORATION COMMISSION
 Wichita State Office Bldg. - PLUGGING SECTION
 130 S. Market, Room 2078
 Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT
 Operator License # 101
 Operator: State Of Kansas Fee Fund
 Name & Phillip Stich (Maloney) Project
 Address _____
 AB oil well XXXXXX Gas Well _____
 Other well as hereinafter indicated: _____
 Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097
 Address: 19450 Ford Road, Chanute, Kansas 66720
 Company to plug at: Hour: _____ Day: 7 Month: 2 2011
 Plugging proposal received from: Jim Kepley
 Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730
 Were: Clean well to TD and then pump full of cement.

Plugging Proposal Received by: Alan M. Dunning
 TECHNICIAN
 Plugging attended by Agent: All _____ Part XXXXXX None _____
 Operations Completed: Hour: _____ Day: 7 Month: 2 2011
 Actual Plugging Report: A 1" pipe was lowered to 350' to check for obstructions. The 1" was
 removed and the well perforated at 300' and 150'. A 1" cement string was then washed down to 750'. The
 well was pumped full of cement from btm to top thru this cement string. A total of 98 sacks of portland
 cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED

FEB 25 2011

Remarks: Control # 20110016-002
 (If additional description is necessary, use BACK of this form.)

I partially observed this plugging

Signed:


 Alan M. Dunning
 TECHNICIAN