

Kansas Corporation Commission
District Plugging Report

API Well Number: 15-121-02124-00-00
 Spot: SESENE Sec 30 Twp 18 S Rng 23 E / W
~~3295~~ 3131 Feet from N / S Line of Section
~~935~~ 614 Feet from E / W Line of Section
 GPS: Lat: 38.455650 Long: 94.901667 Date: 2/22/08
 Lease Name: Whiteford Well #: 03 (WHI-03)
 County: Miami Total Vertical Depth: 405 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>State of Kansas</u>	<u>T1 - Tubing 1</u>	<u>2.000</u>			
Address 1: <u>1500 W. Seventh</u>	<u>PROD - Casing</u>	<u>6.250</u>			
Address 2: <u>Fee Fund</u>	<u>I1 - Casing</u>	<u>8.000</u>			<u>SURFACE CASING</u>
City: <u>Chanute</u>					
State: <u>KS</u> Zip Code: <u>66720</u>					

Well Type: OIL UIC Docket No.: _____ Date/Time to Plug: 1/28/11 / 9:00 am
 Plug Co License No.: 33749 Plug Co. Name: Kepley Well Service, LLC
 Proposal Rcvd from: Jeff Fredricks Company Name: Kepley Well Service, LLC Phone: (620) 433-3489

Proposed Plugging Report: Fill the well full of cement from bottom to top.

Plugging Proposal Received By: Taylor Herman Witness Type: ZERO - None
 Date/Time Plugging Completed: 1/28/11 / 4:00 pm KCC Agent: Taylor Herman

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
PULLED THE 2" TUBING OUT FROM INSIDE 6 1/4". PEFORATED THE 6 1/4" AT 300', 150', AND 75'. WASHE 1" PIPE DOWN TO 405' INSIDE THE 6 1/4" AND PUMPED 96 SACKS OF CEMENT FROM BOTTOM TO TOP ON THE INSIDE AND OUTSIDE OF THE 6 1/4". CUT OFF AND BACKFILLED.		<u>75</u>		<u>CSG - Casing</u>
		<u>150</u>		<u>CSG - Casing</u>
		<u>300</u>		<u>CSG - Casing</u>

RECEIVED
FEB 17 2011
KCC WICHITA

Remarks: Contract #EVT0000100 Control #20110026-003 IRREGULAR SECTION

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No
 District: 03

 (Technician)
 Form: District Plugging Report - _____