

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23348-00-00
Spot: NWSENE Sec/Twnshp/Rge: 11-14S-19W
3630 feet from S Section Line, 990 feet from E Section Line
Lease Name: STADELMAN Well #: 1
County: ELLIS Total Vertical Depth: 3836 feet

Operator License No.: 33723
Op Name: PAUL BOWMAN OIL TRUST
Address: 801 CODELL RD
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	768	0	325 SX
PROD	4.5	3814	0	450 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/14/2010 1:00 PM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: LOUIS "DON" BOWMAN Company: PAUL BOWMAN OIL TRUST Phone: (785) 434-2286

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.
Shoot perms at 2050' - 1475' - 750'.
Casing leak at 3100'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/14/2010 7:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3400' - pumped 100 sxs cement with 500# hulls.
Pulled tubing to 2500' - pumped 100 sxs cement.
Pulled tubing to 1250' - pumped 75 sxs cement - good circulation of cement.
Pulled tubing out - tied onto backside - squeezed with 25 sxs cement.
S.I.P. 100#.
Filled 4 1/2" with 100 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3821	3825		
3556	3560		
3532	3536		
3520	3524		
3460	3466		

INVOICED


Remarks: SWIFT CEMENTING COMPANY-TICKET #17695.

INV. NO. _____

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

JUL 15 2010

RECEIVED
JUL 22 2010
7-22-10
KCC WICHITA

L.G. STEPHENSON & COMPANY, INC
7704 E. KELLOGG, #670


REPLACEMENT CARD
#1 STADELMAN

14-14-19W
NW SE NE

WICHITA, KS 67207

CONTR DUKE DRILLING CO., INC. CTY JELLIS

GEOL _____ FIELD WC (RIDGE HILL WEST DISC)



WV 2190. RE. STD. 1/30/83 CARD ISSUED 4/28/83 P. P. 115 BORD. &

API 15-051-23, 348

1245 BWPD
LKC 3514-3669 OA

ARB OH 3814-3897
(NEW PAY = ARB OIL)

LOG Tops _____ Depth/Bottom

ANR	1465-1725
TOP	3186-996
HEEB	6440-1250
LANS	3489-4299
BKC	3725-1535
ARB	3812-1622
BTD	3836-1646
LTD	3837-1647

8 518 * 768/325SX, 4 #2 * 3814/450SX
 DST (1) 3500-3520 (LKC) / 60-45-60-45, SB, 1250' GIP, REG 10'
 OGM, 600' BROTHY OIL, 70' MW, SIP 875-845, FP 56-278#
 DST (2) 3528-3569 (LKC) / 60-45-60-45, SB, 120' GIP, REG 120'
 O&GGM (25% OIL), 870' SB, OILY GSY OGM, SIP 847-833#, FP
 83-486#
 DST (3) 3607-3634 (LKC) / 40-40-60-45, WB INCRG TO GB, 310'
 GIP, REG 70' OGM (10% OIL), SIP 833-844#, FP 28-28
 DST (4) 3634-3657 (LKC) / 60-45-60-45, SB, 2300' GIP, REG
 860' GSY OIL, SIP 847-375#, FP 28-189#
 DST (5) 3661-3695 (LKC) / TIMES NA, WB DIED / 25", REG 10'
 SLT OGM, SIP 181-194#, FP 28-28#

INFO RELEASED: 3/28/85 - ADDED DST INFO

NOTE: INFO RELEASED: 5/12/83 - WAS OIL WELL - TIGHT HOUE
(over)

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS