

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22619-00-00
Spot: NESWSWSW Sec/Twnshp/Rge: 21-18S-10W
540 feet from S Section Line, 530 feet from W Section Line
Lease Name: FEIST Well #: 7
County: RICE Total Vertical Depth: 3355 feet

Operator License No.: 31327
Op Name: PAULEY, GARY DBA PAULEY OIL
Address: 314 5TH ST
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	330		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/15/2010 4:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: BILL SANDERS Company: SOUTHWIND DRILLING, INC. Phone: (620) 517-0706

Proposed Plugging Method: 35 SKS ARB., 35 SKS 1200', 35 SKS 950', 35 WKS 380', 25 SKS 60', 30 SKS - RH, 20 SKS - MH

Plugging Proposal Received By: JEFF KLOCK Witness Type: NONE
Date/Time Plugging Completed: 09/15/2010 4:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

THE DRILL PIPE WAS RUN OPEN END TO THE TOP OF THE ARBUCKLE WHERE 35 SKS OF CMT WAS SPOTTED. THE DRILL PIPE WAS PULLED TO 1250', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRILL PIPE WAS PULLED TO 900', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRILL PIPE WAS PULLED TO 380', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRILL PIPE WAS PULLED TO 60', WHERE 25 SKS OF CMT WAS SPOTTED. THE RAT HOLE WAS CIRCD WITH 30 SKS OF CMT. THE MOUSE HOLE WAS CIRCD WITH 20 SKS OF CMT.

INVOICED

Remarks: QUALITY WELL SERVICE 60/40 4% GEL 1/4 LB FLOSEAL

DATE _____
INV. NO. _____

Plugged through:

District: 02

RECEIVED

Signed _____

SEP 23 2010

(TECHNICIAN)

KCC WICHITA