

TO: ✓
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-073-01095-00-00
Spot: S2NESW Sec/Twnshp/Rge: 25-27S-8E
1650 feet from S Section Line, 1980 feet from W Section Line
Lease Name: LEWIS A Well #: 1
County: GREENWOOD Total Vertical Depth: 1848 feet

Operator License No.: 5242
Op Name: PETROLEUM MANAGEMENT, INC.
Address: 14201 E CENTRAL
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1826		25 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.
Proposal Rcvd. from: GARY REED Company: _____ Phone: (316) 655-8775

Proposed Plugging Method: PERFORATE CASING @ 250'. RUN TUBING TO TD OF 1847'. PUMP 50 SXS OF 60/40 POZ + 4% GEL. PULL TUBING AND LET BOTTOM PLUG HARDEN. PUMP CEMENT FROM SURFACE TO CIRCULATE CEMENT OUTSIDE CASING FROM 250' TO SURFACE. LEAVE CASING FULL OF CEMENT FROM 250' FROM SURFACE. PLUGGING METHODS WILL BE CONFIRMED WITH DISTRICT 3 SUPERVISOR.

Plugging Proposal Received By: STEVE KORF WitnessType: NONE
Date/Time Plugging Completed 08/26/2010 12:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

RAN TUBING TO 1842' PUMPED 50 SXS CEMENT, PULLED TUBING, PERFERATED CASING @ 280' PUMPED 375 SXS CEMENT INSIDE & OUTSIDE OF CASING, CEMENT SETTLED DOWN CASING RAN 1" OUTSIDE OF CASING TAGGED @ 31' RAN 1" INSIDE OF CASING 35 SXS CEMENT, TOTAL CEMENT USED 460 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
1826	1847		PERU SAND OPEN

RECEIVED

AUG 30 2010

KCC Chanute Dist. #3

INVOICED

DATE

Remarks:

INV. NO. _____

Plugged through: TBG

District: 03

Signed

Mike H. [Signature]
(TECHNICIAN)

RECEIVED

SEP 20 2010

Form CP-2/3

KCC WICHITA