

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-21036-00-01  
Spot: NENWNESW Sec/Twnshp/Rge: 24-16S-30W  
2362 feet from S Section Line, 3588 feet from E Section Line  
Lease Name: DUANE Well #: 4-24  
County: LANE Total Vertical Depth: 4593 feet

Operator License No.: 31142  
Op Name: PETROLEUM PROPERTY SERVICES, IN  
Address: 125 N MARKET SUITE 1251  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4040		WITH 2 SX CMT
SURF	8.625	344		WITH 190 SX CMT
DVT		1141		WITH 225 SX CMT
PROD	4.5	4578	0	WITH 150 SX CMT

Well Type: EOR UIC Docket No: E27033.1 Date/Time to Plug: 08/05/2010 1:00 PM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.  
Proposal Rcvd. from: LEON KUHN Company: PETROLEUM PROPERTY SERVICE Phone: (785) 483-1559

Proposed Plugging Method: SET CIBP @ 4100' & 2 SX CMT. RIH W/TBG TO 2250'. CIRCULATE CMT TO 0'. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/05/2010 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4040' WITH 2 SX CMT. RUN TBG TO 2250' & PUMP 130 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE AND PUMPED 15 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4176	4188		LANSING

INVOICED

DATE

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

INV. NO. \_\_\_\_\_

Plugged through: TBG

District: 01

RECEIVED  
AUG 10 2010  
KCC DODGE CITY

Signed Michael Maier  
(TECHNICIAN)

RECEIVED

AUG 12 2010

KCC WICHITA

Form CD 33