

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-21174-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 36-16S-30W  
2970 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: JENNISON Well #: 1-36  
County: LANE Total Vertical Depth: 4617 feet

Operator License No.: 31142  
Op Name: PETROLEUM PROPERTY SERVICES, IN  
Address: 125 N MARKET SUITE 1251  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4300		WITH 2 SX CMT
SURF	8.625	343		WITH 190 SX CMT
DVT		1218		CEMENTED TO SURFACE
PROD	4.5	4615	0	WITH 104 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/05/2010 9:00 AM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.  
Proposal Rcvd. from: LEON KUHN Company: PETROELUM PROPERTY SERVICE Phone: (785) 483-1559

Proposed Plugging Method: CIBP @ 4300' & 2 SX CMT. RIH W/TBG TO 2250' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/05/2010 11:45 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4300' WITH 2 SX CMT. RUN TBG TO 2250' & PUMP 105 SX CMT. CMT CIRCULATED TO SURFACE. TOP OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4514	4519		CHEROKEE
4482	4487		CHEROKEE
4455	4462		FT SCOTT
4424	4434		PAWNEE
4374	4382		LANSING

INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

DATE \_\_\_\_\_

Plugged through: TBG

INV. NO. \_\_\_\_\_

District: 01

Signed \_\_\_\_\_

*Michael Maier*  
(TECHNICIAN)

RECEIVED

AUG 10 2010

KCC DODGE CITY

RECEIVED

AUG 12 2010

KCC WICHITA

Form CP-83