

110-50

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23897-00-00
Spot: NWNESE Sec/Twnshp/Rge: 34-7S-20W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: JANIE LOWRY Well #: 1
County: ROOKS Total Vertical Depth: 3400 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	13.38	47	0	w/90 sxs cmt

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/19/2010 8:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ANDY DINKEL Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 320 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/19/2010 10:45 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 3360' w/25 sxs.
2nd. Plug at 1472' w/50 sxs.
3rd. Plug at 800' w/100 sxs.
4th. Plug at 250' w/100 sxs.
Surface pipe full.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

INVOICED
DATE 12/07/10
INV. NO. 2011060290

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

RECEIVED
Form CP-2/3
OCT 25 2010

OCT 20 2010

KCC WICHITA