

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20250-00-00  
Spot: NWNENWSE Sec/Twnshp/Rge: 21-14S-10W  
2355 feet from S Section Line, 1926 feet from E Section Line  
Lease Name: VOPAT A Well #: 12  
County: ELLSWORTH Total Vertical Depth: 2901 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	359		225 SXS CMT
PROD	4.5	2901		75 SXS CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/27/2010 10:00 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORP Phone: (785) 483-1821

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: SHANE JONES Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/28/2010 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, CK BOTTOM. RUN TUBING TO 2770' AND PUMP 35 SK'S CEMENT WITH CALCIUM CHLORIDE. LET SET FOR 1-1.5 HOURS AND TAG CEMENT @ 1725'. PERFORATE @ 1200', 850' AND 409'. RUN TUBING TO 1200' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 850' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 409' AND CIRCULATE CEMENT TO SURFACE. SHUT VALVE ON CASING - PUMPED 165 SX'S CEMENT, STARTED GETTING SLIGHT RETURNS OUT OF SURFACE CASING. PULL TUBING OUT AND TOP OFF. CAME BACK ON 9-28-2010 AND TOPPED OFF 4.5" CASING WITH 10 SX'S CEMENT AND SURFACE CASING WITH 15 SX'S CEMENT. USED 300 SX'S CEMENT TOTAL AND 300 #'S COTTON HULLS.

Top	Bot	Thru	Comments
2819	2839	CSG	

Remarks: 60-40 POZ, 4% GEL. QUALITY WELL TICKET #4250 AND 9-27-2010 AND #4575 ON 9-28-2010. PERF TECH #7664.

Plugged through: TBG

District: 02

Signed

*Virgil Clothier*

(TECHNICIAN) RECEIVED

OCT 06 2010

Form CP-2/3

KCC WICHITA

ix